

May, Sudweeks & Browning, LLP

Attorneys at Law

JAY D. SUDWEEKS, PC
J. DEE MAY, PC
BART D. BROWNING, CHTD.
J. JUSTIN MAY

jmay@may-law.com

1419 W. Washington
P.O. Box 6091
Boise, Idaho 83707
Telephone (208) 429-0905
Facsimile (208) 342-7278

Twin Falls, Idaho
516 Second Street East
P.O. Box 1846
83303
Telephone (208) 733-7180
Facsimile (208) 733-7967

June 1, 2004

Mr. Jay Engstrom
Idaho Department of Commerce and Labor
P.O. Box 83720
Boise, ID 83720-0093

RE: Rangen, Inc.
Applications for Aquifer Mitigation Assistance Grants

Dear Mr. Engstrom:

Rangen, Inc. operates an aquaculture facility with water rights in the Thousand Springs Reach. Like other springs in the Thousand Springs complex, the source of Rangen's water rights, the Curren Tunnel, has been in decline. Out of total rights for approximately 76 cfs, Rangen is currently receiving only approximately 10 cfs. This is far below the minimum necessary for the operation of Rangen's facility.

Rangen's water rights are senior in priority to many of the ground water rights on the Eastern Snake Plain Aquifer, which is hydrologically connected to the Thousand Springs and Curren Tunnel. As a result of the continuing decline in the water from the Curren Tunnel, Rangen was compelled in September 2003 to initiate a call for water to protect its senior rights. Rangen's call resulted in a February order from the Department of water resources curtailing junior ground water use in Water District 130 after April 1, 2004.

In an effort to avoid the harsh impact that the Director's order would have had on those subject to curtailment and to protect Rangen's interests and continuing operations, Rangen actively participated in the negotiation of the Eastern Snake Plain Aquifer Mitigation, Recovery and Restoration Agreement for 2004. This Agreement prevented the curtailment ordered by the Director and gave all parties a one year opportunity to seek more permanent solutions.

Rangen is fully committed to finding a long term solution to the situation that resulted in the Director's February 2004 order. Any water that can be developed at Rangen's facility will benefit not only Rangen, but also many other water users. Those junior ground water users above Rangen's facility that might be subject to curtailment

would be less likely to face future curtailment. Because Rangen's aquaculture use is nonconsumptive, any water developed for the facility will flow through and be available for use by water users below the facility.

As part of the ongoing effort to find long term solutions Rangen is evaluating several potential options for augmenting water supplies for the Rangen aquaculture facility. The initial list of options includes the following:

1. Divert Curren Tunnel water currently used for agricultural irrigation to the Rangen facility.
2. Withdraw water from a vertical well (or wells) located at the Rangen facility;
3. Construct a horizontal well (or wells) near the Curren Tunnel and at an elevation below the Curren Tunnel;
4. Augment Curren Tunnel flows using water from Weatherby Springs/Hoagland Tunnel;
5. Reduce, if present, downward vertical flow through existing wells in the area upgradient of the Curren Tunnel;
6. Treat and re-use water from the Rangen aquaculture facility.

Under this cover letter, Rangen is submitting applications for financial assistance as part of the Aquifer Mitigation Assistance Grant Program for the first three of these options.

The first application consists of piping water from the Sandy pipeline (constructed in 2003) to a small portion of land owned by Walter and Margaret Candy. The second proposal consists of evaluating the feasibility of withdrawing water from a vertical well located below the canyon rim at the Rangen facility. The third application proposes an evaluation of the feasibility of constructing a horizontal well located near, but below, the Curren Tunnel. The advantages of each of these potential projects, if successful, are that they would provide additional water for the Rangen facility, which would benefit both upgradient ground water users and downstream surface water users.

The fourth option, consisting of piping approximately 0.7 cfs (originating from the Hoagland Tunnel) to the Rangen facility prior to use for irrigation was found to be infeasible. It was originally believed that there might be as much as 4 or 5 cfs of spring water from this source that was not being utilized for aquaculture prior to being used for irrigation. Further research showed that only 0.7 cfs was potentially available, that it was only available at certain times, and that it was contemplated as part of a similar plan in a more proximate aquaculture facility. We believe that the fifth option – evaluation of potential downward flow in wells upgradient of the Curren Tunnel – has merit, and may be best accomplished by the Idaho Department of Water Resources. The sixth option, consisting of pump-back and treatment of water within the Rangen facility, also may have merit. Rangen is currently investigating the feasibility of this option.

Mr. . Jay Engstom
June 1, 2004
Page 3

Thank you for your assistance. If you have any questions, please contact me or our technical consultants SPF Water Engineering, LLC.

Very truly yours,

MAY, SUDWEEKS & BROWNING, LLP

A handwritten signature in black ink, appearing to read "Justin May", with a long horizontal line extending to the right.

J. Justin May

Enclosures
cc: Wayne Courtney

Eastern Snake Plain Aquifer Mitigation Program

**APPLICATION FOR FINANCIAL
ASSISTANCE TO EVALUATE THE
FEASIBILITY OF A HORIZONTAL WELL IN
THE VICINITY OF THE CURREN TUNNEL**

Submitted to:

**The Idaho Department of Commerce and Labor
Division of Economic Development
P.O. Box 83720
Boise, ID 83720-0093**

Submitted by:

**Rangen, Inc.
P.O. Box 706
Buhl, ID 83316**

June 1, 2004

Table of Contents

ESPAM Assistance Grant Application.....	1
Attachment A - Budget.....	2
Attachment B: Scope of Work.....	3
1) Project Description.....	3
2) Purpose and Objectives.....	7
3) Project Tasks.....	7
4) Project Schedule.....	10
5) Cost Details.....	11
6) Potential Benefits and Risks.....	11
7) Summary Discussion.....	13
8) References.....	13

List of Figures

Figure 1: Rangen aquaculture facility.....	3
Figure 2: Major springs in the Milner to King Hill reach of the Snake River.....	4
Figure 3: Average annual discharge rates from the Rangen, Inc., Aquaculture Facility.....	5
Figure 4: Approximate location of cross section shown in Figure 5 (adapted from Covington and Weaver, 1989).....	6
Figure 5: Schematic cross section just north of Hoagland Tunnel/Weatherby Spring (from Covington and Weaver, 1989).....	6
Figure 6: Rangen, Inc. property. Likely drilling area is shown in yellow.....	9

List of Tables

Table 1: Rangen water rights.....	4
Table 2: Water rights to flow from the Curren Tunnel, excluding those held by Rangen, Inc.	10
Table 3: Tentative project schedule.....	11
Table 4: Budget details.....	12

ESPAM ASSISTANCE GRANT APPLICATION

Applicant: Rangen, Inc. Phone: 208-543-6421

Address: P.O. Box 706, Buhl, ID 83316

Application Prepared By: SPF Water Engineering, LLC Phone: (208) 383-4140

Address: 600 East River Park Lane, Suite 105, Boise, ID 83706

Technical Service Provider: SPF Water Engineering, LLC Phone: (208) 383-4140

Address: 600 East River Park Lane, Suite 105, Boise, ID 83706

Water Right Number(s): 36-15501, 36-02551, 36-07694

Amount of Water Supply Reduction: Approximately 80%

PROJECT FINANCING OVERVIEW: ESPAM: \$ 132,928
Private: \$ _____
Federal: \$ _____
Other: \$ _____
TOTAL: \$ 132,928

DESCRIBE PRIVATE/FEDERAL/OTHER MATCHING FUNDS: _____

BRIEF PROJECT DESCRIPTION: Feasibility evaluation of a horizontal well in vicinity of Curren Tunnel; primary task consists of installation of three test wells on canyon rim above Curren Tunnel

APPLICATION CERTIFICATION: The data in this application is true and correct. The undersigned has the authority to submit this application on behalf of the Applicant and will comply with all required certifications, laws, and regulations if the application is approved and selected for funding.

Name: (typed) J. Wayne Courtney Title: Executive Vice President

Signature: _____ Date: _____

Name: (typed) May, Sudweeks & Browning Title: Attorneys for Rangen, Inc.

Signature:  Date: 6-1-04

ATTACHMENT A - BUDGET

Grantee: Rangen, Inc. Project No.: _____

Project: Feasibility Evaluation of a horizontal Well in Vicinity of Curren Tunnel

LINE ITEMS	AMOUNTS				Total
	ESPAM Grant	Private	Federal	Other	
Construction and Project Improvement (includes equipment)	67,000				\$67,000
Professional/Engineering Fees	43,773				\$43,773
Contingency	22,155				\$22,155
Total Costs	\$132,928	\$	\$	\$	\$132,928

1) Project Description

a) Background

Rangen, Inc. ("Rangen") is one of the largest suppliers of high-yield, low waste feeds for the aquaculture industry. Rangen conducts on-going nutrition research to improve aquaculture feeds and husbandry practices. Rangen feeds are then tested in its aquaculture facility near Hagerman, Idaho to measure performance under practical conditions.

The Rangen aquaculture facility (Figure 1) is located in Gooding County approximately 3 miles from Hagerman, Idaho. The primary water source for the Rangen facility (Table 1) is spring discharge from the Curren Tunnel¹. This is one of many springs in the Milner to King Hill reach of the Snake River (Figure 2) that collectively form a primary discharge area for the Eastern Snake River Plain (ESRP) aquifer.




Figure 1: Rangen aquaculture facility.

¹ Also known as the Martin-Curren Tunnel.

Number	Priority Date	Decreed Date	Source	Maximum Diversion Rate	Maximum Diversion Volume
36-135A	Apr 1 1908	Aug 27 2001	Martin-Curren Tunnel	0.050	0.000
36-15501	Jul 1 1957	Dec 29 1997	Springs	1.460	0.000
36-2551	Jul 13 1962	Dec 29 1997	Martin-Curren Tunnel	48.540	0.000
36-10269	Aug 5 1976	Nov 22 1996	Ground Water	0.040	0.000
36-7694	Apr 12 1977	Dec 29 1997	Springs	26.000	0.000
36-8048	Dec 21 1981	Aug 27 2001	Ground Water	0.410	80.800
36-134B	Oct 9 1884	Aug 27 2001	Martin-Curren Tunnel	0.090	0.000

Table 1: Rangen water rights.




Figure 2: Major springs in the Milner to King Hill reach of the Snake River.

Numerous springs in the Milner – King Hill reach have experienced decreased flows in recent years (Bendixsen, 1995; Johnson et al., 2002). Average annual diversion rates (based on average monthly diversions) to the Rangen facility from the Curren Tunnel were over 50 cfs during the 1960s and early 1970s, but have decreased to less than 15 cfs in recent years (Figure 3).




Figure 3: Average annual discharge rates from the Rangen, Inc., Aquaculture Facility.

The Curren Tunnel draws water from a pillow lava facies of the Malad Basalt (Johnson et al., 2002). Review of a geologic cross section (Figure 5) of the vicinity of the Curren Tunnel (Figure 4) compiled by Covington and Weaver (1989) suggests that discharge at the Curren Tunnel may be controlled, in part, by clay zones associated with the Yahoo Clay or varying permeability characteristics of the Malad Basalt.

b) Project Description

One alternative for increasing spring flows to the Rangen facility would be to construct a horizontal well in the vicinity of, but at an elevation below, the Curren Tunnel. The purpose of the horizontal well would be to tap ground water in the vicinity of the Curren Tunnel, but doing so in the context of decreased local ground water levels. Such a horizontal well in the vicinity of the Curren Tunnel could be considered a "well deepening" of the current Curren Tunnel discharge point.

The major benefit of a horizontal well is this: if successful, a horizontal well could provide substantial increase in flow to the Rangen facility without requiring new water rights, mitigation for potential new withdrawals from vertical wells located at the Rangen facility, or ongoing operational costs and water quality concerns associated with various pump back strategies.




Figure 4: Approximate location of cross section shown in Figure 5 (adapted from Covington and Weaver, 1989).




Figure 3. Schematic section of the canyon wall near profile-control location 179-1 east of Hagerman. Section shows the interpretative relation of the confining units of Yahoo Clay and Glenns Ferry sediments to the Malad Basalt canyon filling deposits.

Figure 5: Schematic cross section just north of Hoagland Tunnel/Weatherby Spring (from Covington and Weaver, 1989).

A major question associated with the construction of a horizontal well would be the availability of water at a point lower than the Curren Tunnel. Most of the natural springs in the vicinity of the Curren Tunnel discharge from a similar elevation, suggesting that a common geologic feature is controlling the discharge elevation. Such controls might include the presence of Yahoo Clay, Glens Ferry sediments, other interflow sediments, or a less permeable portion of the Malad Basalt. Installing a horizontal well below the elevation of the Curren Tunnel risks missing the permeable zone that currently supplies water to the Curren Tunnel.

Drilling of a horizontal well can be expensive, costing approximately \$500 per linear foot (Jack Seburn, North American Construction). A 300-foot long horizontal bore (24" diameter) with drilling and associated costs could cost more than \$250,000. One approach to better define horizontal-well target zones would be to construct one or more vertical test wells. Test wells located above the canyon rim, but close to the Curren Tunnel, could be used to define subsurface lithology, water levels, vertical hydraulic gradients, and aquifer characteristics. Multiple vertical test wells would be less expensive than a horizontal test well, and would better enable evaluation of the feasibility of horizontal well to provide water to the Rangen facility.

2) Purpose and Objectives

The purpose of this proposed project is to increase natural flows to the Rangen aquaculture facility. The general objective is to evaluate the feasibility of a horizontal well located in the vicinity of the Curren Tunnel to supply natural flow to the Rangen facility. Specific objectives include the following:

- a. Review local hydrogeologic conditions based on existing information.
- b. Drill three vertical test wells on the canyon rim in the vicinity of the Curren Tunnel; evaluate subsurface lithology and hydrogeologic characteristics in the vicinity of the test wells based on of drill cuttings, drilling resistance, test pumping, water level measurements, etc.
- c. Evaluate the feasibility of a horizontal well based on test-drilling results.
- d. If a horizontal well appears feasible, develop a construction plan and cost estimate for a horizontal production well near the Rangen facility.

3) Project Tasks

a) Evaluate Hydrogeologic Conditions

The first task will consist of a detailed review of hydrologic and geologic information in the vicinity of the Curren Tunnel. The task will include refinement of several cross-sections (including field-verification of well locations) for insight into characteristics of the Malad Basalt in this area. The task will include obtaining and plotting the timing of

surface water flow and ground water extraction patterns with respect to Curren Tunnel Hoagland Tunnel, local well hydrographs, and other available spring-flow data. These and other data will be used to identify test well locations.

b) Well Construction and testing

Well construction and testing will include the following subtasks:

- Selection of drilling location
- Preparation of well design documents
- Solicitation of drilling bids
- Drilling supervision
- Geophysical logging
- Hydraulic gradient testing
- Aquifer testing

Three test wells are envisioned on the canyon rim above the Rangen facility, within approximately 400 feet of the canyon rim (Figure 6). Three wells located on the canyon rim could provide a lithologic description in three general directions from the Curren Tunnel, and would provide basis for determining local potentiometric surface.

The drilling location probably will be limited to property owned by Rangen, Inc. These wells will be used to evaluate hydrogeologic conditions (e.g., aquifer materials, relative permeability, etc.) to the maximum depth that would be considered for a horizontal well. Two of the test wells will be between 150 and 175 feet deep. The third test well may extend to a depth of approximately 300 feet. The latter well will provide similar information as the first two wells, but will also provide subsurface information (geology, gradients, etc) for zones underlying the elevation of a possible horizontal well.

Eight-inch diameter test wells will be constructed using air-rotary drilling. Once below the water table, test pumping and water level checks will generally be conducted with every additional 20 feet of depth (coinciding with drill-stem lengths). Each test-pumping cycle may require removing the drill stem and lowering a test pump capable of pumping between 100 and 300 gallons per minute. Water levels will be monitored prior to and during pumping.

Camera surveys, geophysical logging, and/or borehole flow measurements will be conducted in each well prior to well completion. This information will be used to complete these wells as monitoring wells. The wells will be completed with seals, if necessary, to avoid substantial vertical flows within the boreholes. Completed as monitoring wells, the test wells will provide long-term, dedicated water level information for the vicinity of the Curren Tunnel.

A geologist will be on-site during drilling to monitor drill cuttings, fluid levels, and aquifer testing. Test well locations will be estimated using a global positioning system device; relative elevations will be surveyed following well completion.

A summary report will be completed following test well construction and testing. The report will include a drilling description, detailed well logs, lithologic descriptions, camera survey and/or geophysical interpretations, and other data.




Figure 6: Rangen, Inc. property. Likely drilling area is shown in yellow.

c) Evaluate Feasibility of Horizontal Well

An evaluation of horizontal well feasibility will be prepared based on the test drilling results. This evaluation will have three components. The first component will consist of an evaluation of horizontal well feasibility based on test-well drilling, vertical and horizontal hydraulic gradient analysis, and aquifer testing results, and on discussions with horizontal drilling contractors.

The second component will be an evaluation of potential effects on other water users. As of 2003, most of the water required by Curren Tunnel water-right holders (Table 2) users is being delivered through a recently-installed pipeline that transports irrigation water from the Northside Canal Company and rental pool water. This water is delivered in lieu of water from the Curren Tunnel. However, the rights to withdraw water from the Curren Tunnel have been maintained. If water deliveries in the pipeline are not possible (e.g., if rental water is unavailable) these users are still entitled to draw water from the Curren Tunnel (Jeff Martin, North Snake Ground Water District, *personal communication*, 5/24/04). If a new, successful horizontal well is installed

below the elevation of the Curren Tunnel, there may be insufficient head for gravity feed from the horizontal well to the places of use, requiring mechanical lift. Furthermore, a successful horizontal well may produce more water than is currently flowing from the Curren Tunnel. Some of the additional water (up to the full allotment based on priority dates) might be claimed by the other Curren Tunnel users. An agreement resolving these issues might be required before the construction of a horizontal borehole in the vicinity of the Curren Tunnel commences.

Water Right	Priority Date	Owner	Maximum diversion rate (cfs)			
			Irrigation	Stockwater	Domestic	acres
134A	10/9/1884	Walter and Margaret Candy	0.49	0.04	-	36
135B	4/1/1908	Walter and Margaret Candy	0.51	-	-	36
134D	10/9/1884	Howard and Rhonda Morris	1.58	0.06	-	143
135D	4/1/1908	Howard and Rhonda Morris	1.58	0.06	-	143
10141A	12/1/1908	Howard and Rhonda Morris	0.82	0.03	-	143
134E	10/9/1884	Howard and Rhonda Morris	0.82	0.04	-	75
135E	4/1/1908	Howard and Rhonda Morris	0.82	0.02	-	75
10141B	12/1/1908	Howard and Rhonda Morris	0.43	0.02	-	75
102	4/1/1892	J Alvin Musser	4.1	0.07	0.04	205
Total			11.15	0.34	0.04	931

Table 2: Water rights to flow from the Curren Tunnel, excluding those held by Rangen, Inc.

In addition, it is possible that lower horizontal well near the Curren Tunnel may lead to decreases in local ground water levels outside of the immediate Curren Tunnel area. An analysis of responses in surface water applications, ground water withdrawals, and spring flows in the Curren Tunnel and Hoagland Tunnel (to the extent that data are available) may give insight into this question (Task 3a). These factors will be considered in analyzing the feasibility of a horizontal well.

The third component – a construction plan for a horizontal test well – will be prepared if it is determined that a horizontal well would represent a feasible solution to supplying additional water to the Rangen facility. The plan would contain drilling specifications, estimated costs, and other information required to proceed with construction of a horizontal well.

4) Project Schedule

A tentative project schedule is shown in Table 3. The schedule assumes a start time of August 2004.

Tentative Schedule							
Task	Aug 2004	Sep 2004	Oct 2004	Nov 2004	Dec 2004	Jan 2005	Feb 2005
a) Evaluate Hydrogeologic Conditions	x						
b) Obtain drilling bids, construct test wells, evaluate hydrogeologic characteristics		x	x	x	x		
c) Evaluate Feasibility of Horizontal Well; develop horizontal well construction plan				x	x	x	
Submit Final Report							x

Table 3: Tentative project schedule.

5) Cost Details

Preliminary costs for this project are shown in Table 4. These costs are greater than general well-drilling costs because of frequent water level measurements and test pumping during drilling, the presence of an on-site engineer/geologist during drilling and testing, and pre- and post-drilling analyses. These costs will be refined on the basis of final well specifications and contractor bids.

6) Potential Benefits and Risks

a) Potential Benefits

A successful horizontal well could result in a substantial increase in flow to the Rangen facility. Rangen's facility is nonconsumptive. Increased water flow through the Rangen facility will benefit not only those junior users in the Snake River Plain that could be subject to curtailment, but would also benefit water users downstream of the Rangen facility. The Department of Water Resources has indicated that a horizontal well in this location would be analogous to a "well deepening." Therefore, administratively, this horizontal well would be much simpler than a new vertical well. If constructed at an elevation greater than the Rangen aquaculture facility, the horizontal well would not require operating costs to lift water.

Task	SubTasks	Engineering	Construction and Indirect	Total
a) Evaluate Hydrogeologic Conditions				
	Review of driller reports	944		944
	Field verify well locations	1,216		1,216
	Draw several x-sections in vicinity of Curren Tunnel based on field-verified well locations	1,288		1,288
	Obtain any available ground water extraction estimates for vicinity of Curren Tunnel	200		200
	Obtain Northside canal flows and timing in vicinity of Curren Tunnel	200		200
	Plot canal timing and ground water extraction timing on Curren Tunnel, Hoagland Tunnel, and other hydrographs	1,488		1,488
	Summarize results in brief report	2364		2364
	Subtotal	7,700		7,700
b) Well Construction				
	Prepare well design specifications	1,920		1,920
	Obtain, review bids	1,920		1,920
	Drilling supervision	10,930		10,930
	Geophysical logging	1,180		1,180
	Lithologic descriptions	1,480		1,480
	Geophysical interpretation	960		960
	Summary report	4,248		4,248
	Travel Expenses		1875	1,875
	Subtotal	22,638	1875	24,513
Estimated Contractor Costs				
	Drilling subcontractor (assume 2 wells at 200 ft each and 1 well at 300 ft each for a total of 700 ft. Assume \$85/ft to account for frequent water level measurements and tripping out for test pumping every 20 feet).		59,500	59,500
	Geophysics and/or camera subcontractor; assume \$2,500 per well		7,500	7,500
	Subtotal		67,000	67,000
c) Evaluate Feasibility of Horizontal Well				
	Analysis	2,904		2,904
	Horizontal drilling plan	4,368		4,368
	Presentation with client, discussion with Interim Committee	1,600		1,600
	Summary Report	2,688		2,688
	Subtotal	11,560		11,560
Subtotal				\$110,773
Contingency (20%)				22,155
Total				\$132,928

Table 4: Budget details

The primary immediate benefit of this project would be knowledge. Vertical test wells will provide necessary information to design a horizontal well, and minimize the potential risks of a horizontal well. A horizontal well in the vicinity of the Curren Tunnel may lower local hydraulic heads, which may lead to decreased flows in the Curren Tunnel and possibly other springs in the vicinity of the Curren Tunnel. Some analysis of hydrologic characteristics in the vicinity of the Curren Tunnel, other springs (e.g., Hoagland Tunnel), and fluxes above the canyon rim (e.g., spring canal filling, summer ground water withdrawals, etc.) may give insight into this question (Task 3a).

Provisions would need to be considered to shield other Curren Tunnel users with rights more senior to that of Rangen from the effects of reduced flow. Options for doing so would be identified as part of Task 3c. The vertical test wells and associated evaluations will be completed by February 2004.

b) Potential Risks

There are several potential risks associated with this project. The first is that test drilling may not reveal a promising zone into which to drill a horizontal well. The second risk is that a promising zone is identified, but the horizontal well, if constructed, is unable to produce a sufficient amount of water. It is also possible that the concerns listed above cannot be adequately addressed and therefore a horizontal well would not be feasible.

7) Summary Discussion

This proposed project consists of constructing a series of vertical test wells to determine feasibility of a horizontal well in the vicinity of the Curren Tunnel. A successful horizontal well to replace decreased flows to the Rangen aquaculture facility may provide a long-term solution to diminished flows that are constraining the Rangen aquaculture operation. Increasing flows to the Rangen facility would provide a major benefit to other water users that may be affected by decreased flows to the Rangen facility.

The success of a horizontal well design based on the proposed test wells is not guaranteed. Test drilling may not indicate productive targets for a horizontal well. Potential targets based on test drilling may or may not result in a successful horizontal well. A successful horizontal well may have adverse impacts on flows to the Curren Tunnel and surrounding water levels.

8) References

Bendixsen, S., 1995. Summary of Ground Water Conditions at the Curren Tunnel near Hagerman, Idaho, Idaho Department of Water Resources (Draft Report).

Covington, H.R. and Weaver, J.N., 1989. Geologic Map and Profiles of the North Wall of the Snake River Canyon, Bliss, Hagerman, and Tuttle Quadrangles, Idaho. U.S. Geological Survey, Miscellaneous Investigations Series, Regional Aquifer System Analysis Program.

Johnson, G.S. et al., 2002. Spring discharge along the Milner to King Hill Reach of the Snake River, Idaho Water Resources Research Institute.