BID SCHEDULE

Priest Lake Water Management Project Outlet Dam Improvements

BASE BID (Bid all items)					
Item No.	Description	Estimated Quantity	Unit	Unit Price	Total Price
1	Mobilization/Demobilization (10%)	1	LS		
2	Environmental Protection, Site Prep, and Site Restoration	1	LS		
3	Temporary Access Road/Structure and River Crossing	1	LS		
4	Construction Surveying	1	LS		
5	Cofferdams and Dewatering	1	LS		
6	Excavation and Disposal - Streambed	2,010	CY		
7	Concrete - Apron Scour	10	CY		
8	Reinforced Concrete - Apron Extension	365	CY		
9	Concrete Repair - Pier 6 Spalled Areas	36	CF		
10	Miscellaneous Steel - Strengthen Tainter Gate Skin Plate	11	BAY		
11	Miscellaneous Steel - Tainter Gate Extension	11	BAY		
12	Miscellaneous Steel - Replace Trunnion Pins	11	BAY		
13	Replace J-Seals	11	BAY		
14	Repair Expansion Joints - N & S Abutment Wing Walls	100	LF		
15	Railing - Repair Damaged Section	8	LF		
16	Replace Grease Fittings and Pump	11	BAY		
17	Install New Gauge on North Abutment and South Abutment	2	EA		
18	Vibrating Piezometer Array	1	LS		
19	Armor Stone	2,070	TON		
20	Bedding Stone	1,390	TON		
21	Crushed Rock Base Course	37	TON		
22	Geotextile Fabric	621	SY		

23	Approach Redevelopment - Base Course	~~39~~ **230**	TON		
24	Approach Redevelopment – Top Course	~~20~~ **200**	TON		
25	Approach Redevelopment – Hot Mix Asphalt Paving	25	TON		
26	Minor Changes	1	~~LS~~ **EST**	**$10,000**	

TOTAL BASE BID PRICE (Sum of Item No. 1 through Item No. 26):

$_____

TOTAL BASE BID PRICE (IN WORDS)

_____

Submitted on_____ (Date)